



OTSG 616

Precautions During Signal Testing

Applicability

NSW

SMS

Publication Requirement

Internal Only

Document Status

Issue/Revision #	Effective from
1.0	1 January 2019



Purpose

To prescribe the precautions required during signal testing in the *Oberon Tarana Heritage Railway (OTHR) Network*.

General

Changing signal indications

A signal *must* not be tested if:

- *rail traffic* is *closely approaching*, and
- the testing could change the signal indication.

If rail traffic is standing at a signal at STOP, the *Signaller* must:

- before testing the signal, tell the *Driver* or *track vehicle operator* that their *train* or *track vehicle* must not move unless instructed to do so, and
- after testing the signal, tell the *Driver* or *track vehicle operator* that the testing has been completed and, if required, give an authority to proceed.

Recording test results

Signallers and *Qualified Workers* must record signal test results in *permanent form*.

Related OTHR Network Procedures

OTPR 721	Spoken and written communication
----------	----------------------------------

Effective Date

1 January 2019